

TYPICAL FOOTER SOUTH RETAINING WALL

D

CONCRETE RETAINING WALL

1/2" REBAR HORIZONTALS 2' OC AND VERTICAL TIES 4' OC

2500 PSI CONCRETE FOOTER

3 - 1/2" REBAR HORIZONTALS AND WITH CROSS TIES

C/W XPS INSULATION ON ALL EXTERIOR FOOTERS AND WALLS TO "Frost Proof Shallow Foundation" SPEC

FERROCEMENT PLANTER WALL

HORIZONTAL 1/2" REBAR

VERTICAL 1/2" REBAR 2' OC

PLASTER LATHE REINFORCED FERROCEMENT 2 1/2" NOM. THICKNESS

HORIZONTAL 1/2" REBAR

FINISHED INTERIOR FLOOR LEVEL

SAND BEDDED BRICK PAVERS

PER FLOOR PLAN

12" X 1/2" ANCHOR BOLT 4' OC

2 X 8 P.T. SILL

2X2 GALV. 16 GAUGE STEEL TYP. GREENHOUSE FRAMING VERTICALS 48" OC

"LEXAN" TRIPLE WALL POLYCARBONATE TYP. FOR ALL GREENHOUSE WALLS AND ROOF

3" #10 HEX HEAD FASTENERS 12" OC

1 1/2" #10 HEX HEAD FASTENERS 6" OC

2" EXTRUDED FOAM FLASHED WITH 45 MIL EPDM RUBBER MEMBRANE

MAXIMUM HEIGHT OF EXTERIOR GRADE

HORIZONTAL 1/2" REBAR 2' OC TYP.

VERTICAL 1/2" REBAR 4' OC

8 X 8 X 16 BLOCK SOLID GROUT TYP.

HORIZONTAL 1/2" REBAR 4' OC

2500 PSI CONCRETE FOOTER

INCLUDE PERFORATED FOOTER DRAIN TO DAYLIGHT ON ALL PERIMETER FOOTINGS BED IN 1" WASHED ROCK C/W SOIL SEPARATOR COVER

HORIZONTAL 1/2" REBAR X 3

3'-0" [36"]

4'-8" [56"]

10"

2'-8" [32"]

PLANTER TOPSOIL

PIT RUN BACKFILL

PIT RUN BACKFILL

D'ARRIGO REMODEL

ADDITION TO APACHE COUNTY BP2005-160

DRWG# **151**

ANDY D'ARRIGO - OWNER

(928) 339-4855

DRN BY *jdc*

DICKEY CONST INC - CONTRACTOR

(928) 245-1995

DATE **5/4/06**

SECTION "D" - SOUTH RETAINING WALL TYP.

SCALE **1:16**

GOING CONCERNS UNLTD - DESIGN

(970) 215-4710

REV# **05**

DRWG **DD**